

HEAVY DUTY BOLTLESS 3 TIER SHELVING UNIT

Before you start

- Check pack to ensure you have all the parts listed in the contents.
- When ready to start ensure that you have plenty of space for assembly.
- Take care assembling this shelf unit as there may be some sharp edges or corners.
- The maximum weight loading is 100kg per shelf. If the unit is going to be loaded to its maximum capacity. It must be firmly fastened to the wall using the wall retainers supplied and suitable screws and plugs (not supplied).

Assembly Instructions

- Diagram 1 - Lay out 2 leg pieces on the floor with the tabs up the same way and join together using the short beams. Insert 2 tabs on the leg into the beam and push down to clip into position. 3 beams must be positioned like this, 1 at the top, 1 at the bottom and 1 at a position of your choice between them.
- Diagram 2 - Repeat the process above until you have 2 matching frames as shown.
- Diagram 3 - Using the long beams join the 2 frames together using the same technique, ensuring that the long beams are at the same level as the short beams. Repeat this process until all beams are installed and the unit looks like the diagram.
- Push the plastic feet onto the bottom of each leg.
- Diagram 4 - Stand the unit in position and drop the wooden shelves onto the support beams. Ensure that all beams are fully engaged and pushed down firmly.

